



77205D-PS High Profile Semi-Automatic Stretch Wrapper with 200% Powered Pre-Stretch

If your looking for a heavy-duty, low maintenance stretch wrapper the Powered pre-stretch 77 series is the answer. With this easy to operate machine you load the 48"variable speed turntable, attach the wrap to the load, select a program, press start and walk away. The carriage raises and wraps the load until the photo electric eye senses the top of the load. When the top of the load is sensed a preset number of top wraps are applied. After the number of top wraps the film carriage then reverses itself and continues to wrap the load as it lowers. When it reaches the bottom the turntable stops in the same position that it started for easy unloading. The no-thread powered pre-stretch offers excellent load containment and the best in film savings.

Maximum Load Size:

52" x 52" x 80" (120" Mast Height Available)

Production Capacity:

40 Loads Per Hour

Machine Dimensions:

85"L x 48"W x 83"H

Weight Capacity:

4,000 lbs.

Electrical Data: 120 VAC 60 Hrtz 20 Amps

Conventional Style 3 Prong Power Cord

UL Approved Components

Turntable Size: 48" Round Steel Diamond Deck or 48" Octagon

Steel Diamond Deck with 5" Safety Skirt

Turntable

14 5/8" Height:

Turntable

Drive:

3/4 Hp DC Motor (Totally Enclosed Fan Cooled) Variable Speed Turntable 0 to 15 RPM with Soft

Start and Soft Stop

Lubrication Free Enclosed Gear Drive

Design

Synthetic Lube in all Gearboxes (-30 to 120

Degrees)

Turntable Indexing Home Alignment

Controls:

PLC-Programmable Logic Control with Pre-

Programmed Sequences Turntable Variable Speed Dial Dispenser Variable Speed Dial Film Tension Variable Dial

Turntable Jog

Emergency Štop Button Photo Eye for Automatic Load Height Sensing

On/Pause Button Start/Resume Switch

3 Indicator Light, Power, Ready, and Tension

Liquid Crystal Display



Film Delivery: No-Thread Powered Pre-Stretch

Stretch Level 200% Fixed (Gear Switch to

250% or 300%)

Force to Load Dial for Different Load Weights

Accepts 12" to 20" Rolls of Stretch Film

1/2 Hp DC 90 Volt Motor

Film Carriage: Variable Speed Carriage 0 to 20 FPM

1/4 Hp 90 Volt DC Motor

Dispenser Kill Switch Top / Bottom

Top Over Wrap

Formed All Steel Tower Tower

Construction: 80" Wrap Height (Optional Wrap Height

Available)

#40 Chain Drive Lift **UHMW Full Tower Slides**

Custom Formed 3/8" Steel Channel Frame

> All Welded Steel Construction Easy Access to All Components

Forklift Portable from Front or Rear

3 Year Limited Warranty Warranty: (100% of All components).

Shipping

Construction:

1,340 lb. Weight: